

27. IF ANY PAVEMENT MARKINGS ARE TO BE RELOCATED, VEHICLE DETECTOR LOOPS SHALL BE RELOCATED ACCORDINGLY TO REMAIN CONSISTENT WITH CITY OF RENO STANDARD DETAIL NO. R-406A, R-406B AND R-406C.
28. AS A PART OF ANY STREET WIDENING PROJECT OR THE ADDITION OF ANY STREET TRAVEL LANES TO EXISTING LANES, SUCH AS TURN LANES, ACCELERATION OR DECELERATION LANES, ETC., THE CONTRACTOR MUST EXTEND ANY TRAFFIC CONTROL CONDUITS AND/OR WIRING AND REPLACE ALL AFFECTED VEHICLE LOOP DETECTOR WIRING (SPlicing SHALL NOT BE ALLOWED).
29. SIGNAL EQUIPMENT SHALL BE PROVIDED AND APPROVED THROUGH THE SUBMITTAL PROCESS TO THE PUBLIC WORKS TRAFFIC ENGINEERING DIVISION AT TRAFFICSIGNALS@RENO.GOV.
30. FOR POLE DETAILS NOT SHOWN, SEE POLE MANUFACTURER'S DETAILED DRAWINGS.
31. ALL SIGNAL POLES AND FOUNDATIONS SHALL CONFORM TO NDOT TYPE 35 AND 35A SPECIFICATIONS, INCLUDING BOLT CIRCLE DIMENSIONS, ANCHOR BOLTS, AND FOOTING DIMENSIONS.
32. FINAL POLE APPROVAL AND SUBMITTALS TO BE APPROVED BY THE CITY OF RENO.
33. CLAM SHELL FOR TYPE 7D POLE TO BE USED ONLY WHEN POLE IS INCLUDED AS A SIGNAL POLE. DO NOT USE CLAM SHELL WHEN TYPE 7D POLE IS USED IN SERIES LIGHTING.
34. POLE MAY BE MANUFACTURED AS EITHER A DOUBLE OF SINGLE CANDYCANES CONFIGURATION.
35. VIDEO DETECTION MAY BE USED IF APPROVED BY THE CITY TRAFFIC ENGINEER.
36. ALL EQUIPMENT SHALL BE IN ACCORDANCE WITH CITY OF RENO "TRAFFIC SIGNAL CONTROLLER CABINET SPECIFICATIONS" AND CITY OF RENO "TRAFFIC SIGNAL FIBER OPTIC INTERCONNECT SPECIFICATIONS" EXCEPT AS SPECIFICALLY MODIFIED IN THESE PLANS. NEW CONTROLLER ASSEMBLIES SHALL INCLUDE ALL SIGNAL CONTROLLER EQUIPMENT AS REQUIRED BY THE CITY'S EQUIPMENT SPECIFICATIONS.
37. SIGNAL TURN-ONS SHALL BE SCHEDULED BETWEEN 5:00 AM AND 4:00 PM ON MONDAY THROUGH THURSDAY. COORDINATE WITH CITY OF RENO SIGNAL TECHNICIANS.
38. 1/4"-20 BOLTS WITH LOCK WASHERS AND FLAT WASHERS ARE REQUIRED FOR ALL HAND HOLE AND BASE PLATE COVERS.
39. SIGNAL SHUTDOWNS WILL ONLY BE PERMITTED FROM 9:00 PM TO 5:00 AM IN THE CITY OF RENO, UNLESS OTHERWISE APPROVED FOLLOWING WRITTEN REQUEST.
40. ALL SIGNAL EQUIPMENT, HARDWARE, UNBROKEN PULL BOX LIDS, AND SIGNS REMOVED THROUGH THE COURSE OF WORK SHALL BE DELIVERED TO THE CITY OF RENO'S CORPORATE YARD.



STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION

DRAWING No.

NOTES - TRAFFIC SIGNALS & POLES

R-413H

APPROVED BY: KK

DATE: 2/2026